

### **Full Infield Renovation**

- Removal of all sod on the infield, along the edges of the infield and where the lips of the outfield grass meet the infield playing surface.
- Reestablishing the correct dimensions of the field, lowering the lips to make a smooth transition from infield skin to grass areas and laser grading all areas to be sodded. Resodding all disturbed areas with Kentucky bluegrass sod.
- Removal of the 2" of existing ag lime infield and replacing it with a new DuraEdge Classic 2" cap playing surface. This includes providing the material, settling and rolling, and laser grading the infield skin.
- New base anchors placed, a complete reconstruction of the pitchers' mound to correct dimensions and elevations along with a new pitching rubber. The mound would be built using DuraPitch clay.
- The home plate area will be completely reconstructed and new infield clay will be established to correct elevations and slopes for water drainage. A new home plate, clay batters' boxes along with clay catching areas will be installed as well.

### **Infield irrigation**

- Installing an infield irrigation system that will water the sidelines, infield square, and the grass along the back arc of the infield.

### **Outfield irrigation**

- Installing an outfield irrigation system that will water all areas inside the fence from outfield fence to infield arc. This system would be an add-on to the newly installed infield irrigation system.

### **Back Stop Netting System**

- This will provide the ultimate viewing option for our fans and spectators. Includes providing and installing a back stop tension netting system. The system will include 4 poles that would not interfere with existing concrete and landscaping and not be in viewers way behind the plate. The net would be 40 feet high and extend from dugout to dugout.

### **Back Stop Brick Wall**

- The bottom of the back stop netting will be anchored to a new brick wall that is going to be built by one of our local masonry businesses. As part of that project, we will have a new brick wall that extends from dugout to dugout, with dark colored bricks to match our dugouts and have a logo in the center of it that is viewable by spectators. This undoubtedly will put Mid-Prairie at the top of the conference for best looking fields.

Total estimated costs for these projects are **\$178,000**